2009 CASFM Annual Conference Plenary Session - A Look Back at 1999 CASFM Grand Award 2000 ASFPM James Lee Witt Award

#### Willow Creek Channel Improvements and Sedimentation Pond

Urban Drainage & Flood Control District South Suburban Park and Recreation District Arapahoe County Muller Engineering Company Wenk Associates

## Located in Arapahoe County, South of Dry Creek Road, West of Quebec



## Willow Creek Watershed

- Creek Characteristics:
  - Drainage basin tributary to site is 8.10 square miles
  - Creek bank full capacity 300 cfs
  - Base flow in creek is 5 cfs
  - 2 year storm is 1,650 cfs, 100 year storm is 6,100 cfs
- Design in 1997-98, Construction in 1998-99

## **Project Goals and Objectives**

- Repair Steep eroded bank and Replace Pedestrian Crossings
- Use bioengineering techniques and several types of erosion control fabrics
- Water Quality
  Enhancement Facility







## **Desire for Innovative Solutions**

- Channel Stabilization: Grade Control, Low Flow Crossings, Channel Relocation
- **Cliff Stabilization:** Bio-engineering Techniques
- Sedimentation Pond: Water Quality Retrofit





Before

**Channel Relocation** 

After

## **Engineering Plan Overview**



#### **Drop Structures & Pedestrian Crossings**



#### After Construction



Year 1, 1999





Year 10, 2009

Year 4, 2002

## **Cliff Stabilization - Fill Slope Area**





- Wrapped Soil Lifts
- Brush Layering
- Erosion Control Blanket



#### **Cliff Stabilization - Fill Slope Area**



After Construction



Year 1, 1999





Year 10, 2009

Year 4, 2002

## Inner and Outer Channel Banks





- Coir Rolls
- Permanent Erosion
  Control Mat
- Permanent Geotextile



#### **Inner and Outer Channel Banks**



After Construction



Year 1, 1999



Year 4, 2002



Year 10, 2009

## Wetland Areas

• One area located at storm pipe outlet



 One "backwater" wetland area with gravity low flow pipe to help establishment



#### Wetland Areas



Year 1, 1999, Backwater Wetland



Year 2, 2000, Pipe Wetland



Year 4, 2002, Backwater Wetland



Year 10, 2009, Backwater Wetland

## Willow Creek Sedimentation Pond Criteria Constraints

- Size of existing site could not accommodate capture volume needed for "Wet Pond" (70 ac-ft) or "Sediment Forebay" (5.5 ac-ft)
- Outlet Structure could not be designed for 40 hour emptying time.
- Decision time: do the best we could with the space we have available? How effective will the facility be?



Sediment Pond Location Before Construction "Retrofit" (Best we can)- Design Parameters

- Pond capacity and sediment storage volume is 1000 cubic yards-0.62 ac-ft. Pond designed to trap sediment for base flow and stormwater.
- Base flow of 5 cfs had sediment load estimated at 850 cy per year.
- Permanent pool depth of 8.6 ft
- On Stream Pond with diversion structure, concrete bottom and under drain system

#### **Pond Construction**



#### **Unstable Subsurface Conditions**

#### **Underdrain Construction**



#### **Pond Lining Construction**



#### **Stream Diversion Wall**



#### **Return Flow System**



### **Overflow Spillway**



#### **Pond Construction Complete**



## Pond During Runoff Event



## Sediment Pond Maintenance

- Construction complete in March 1999.
- Sediment pond was full (1000 cy) by July 1999.
- Sediment removed in August 1999, cost was about \$20,000.
- Sediment removed two times a year from 2000-2006, about \$18,000 each time and 1000 cy removed each time.
- Sediment removed one time a year from 2007-2009, 1000 cy each time, less volume due to channel stabilization upstream?

#### Pond Maintenance Access



## Pond Full of Sediment, Drained, and Ready to be Cleaned



#### Sediment Pond Cleaning



#### Sediment Pond 10 years Later



Sediment Pond in 2009 – Diversion Wall Barely shows

## Sediment Pond 10 years Later



# **Concluding Thoughts**

- Project was monitored for several years. No "failures" using "softer" approach. Verified design and construction assumptions.
- Project success lead to modifications in District's Criteria Manuals.
- Sediment pond operation and maintenance has been very successful in keeping sediment from entering Englewood Dam Flood Pool.